

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-03711-00-00  
Spot: SESENE Sec/Twnshp/Rge: 14-16S-14W  
2310 feet from N Section Line, 330 feet from E Section Line  
Lease Name: NETTLEINGHAM (TRAPP UT) Well #: 1-14  
County: BARTON Total Vertical Depth: 3391 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3385		100 SX
SURF	8.625	360		225 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/29/2015 8:30 AM  
Plug Co. License No.: 34612 Plug Co. Name: EXACT WELL SERVICE LLC  
Proposal Rcvd. from: BUD NEFF Company: CHESAPEAKE OPERATING Phone: (260) 277-0803

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 12 sx gel.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/29/2015 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1450' and 900'. Squeezed casing leak at 3245'. Ran tubing to 3200' and pumped 50 sx cement w/50 # hulls. Pulled tubing to 2680' and pumped 12 sx gel. Pulled tubing to 1500' and pumped 225 sx cement w/200 # hulls. Had good circulation of cement until the end of pumping. POOH. Filled casing w/80 sx cement and 150 # hulls. Hooked to braden head and pumped 10 sx cement at 300 psi. Checked casing and fill up later. Casing was full.

GPS: 38.66039 -098.33212

Perfs:

Top	Bot	Thru	Comments
3230	3326		

Remarks: CONSOLIDATED CEMENTING TICKET # 49565

Plugged through: CSG

*10/27/15 ckm*

District: 04

Signed

*Ray Dinkel*

(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

SEP 30 2015

OCT 15 2015

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS