

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-21468-00-00  
Spot: NW Sec/Twnshp/Rge: 15-35S-16W  
1320 feet from N Section Line, 1470 feet from W Section Line  
Lease Name: NEIL Well #: 1-15  
County: COMANCHE Total Vertical Depth: 5600 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5315		WITH 2 SX CMT
CIBP		5420		
PROD	4.5	5600	0	WITH 180 SX CMT
SURF	8.625	1050		WITH 550 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/15/2015 9:30 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 5315' WITH 2 SX CMT. PLUG AT 1080' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/15/2015 11:10 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

10/14/15: SET CIBP @ 5315' WITH 2 SX CMT. WELL WAS GASSY. TRIED TO KILL THE GAS WITH WATER BUT THE WELL STILL BLEW GAS & MUD INTO THE PIT. DECIDED TO TRY PERFORATING & CIRCULATING CMT. 10/15/15: PERFORATED AT 1080'. PRODUCTION CASING DID NOT BECOME GASSY. PUMPED FRESH WATER THROUGH PERFORATIONS BUT STILL HAD GAS ON THE ANNULUS. GAS BLEW DOWN TO A SLIGHT BLOW. PUMPED 405 SX CMT CIRCULATING CMT TO SURFACE. ANNULUS STILL HAD SOME GAS AFTER CIRCULATING. SDON. 10/16/15: TAGGED TOC @ 170' IN 4 1/2" CASING. PUMPED 40 SX CMT DOWN 4 1/2". PUMPED 55 SX CMT DOWN 4 1/2" X 8 5/8". BACKSIDE PRESSURED TO 500 PSI.

Perfs:

Top	Bot	Thru	Comments
5426	5442		
5392	5418		
5366	5386		

KCC WICHITA  
OCT 26 2015  
RECEIVED  
10-26-15

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

10/27/15 CKM

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
OCT 19 2015  
KCC DODGE CITY