

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22261-00-00
Spot: E2SE Sec/Twnshp/Rge: 7-35S-13W
1320 feet from S Section Line, 660 feet from E Section Line
Lease Name: STERNBERGER Well #: 4
County: BARBER Total Vertical Depth: 4994 feet

Operator License No.: 3532
Op Name: CMX, INC.
Address: 1700 N WATERFRONT PKWY BLDG 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4850		WITH 2 SX CMT
CIBP		4967		
PROD	4.5	4993	3200	WITH 150 SX CMT
SURF	8.625	399		WITH 260 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/01/2015 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4850' WITH 2 SX CMT. PLGU AT 625' WITH 10 SX GEL & 50 SX CMT. PLUG AT 425' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: NONE
Date/Time Plugging Completed: 10/01/2015 10:45 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 4850' WITH 2 SX CMT. 1ST PLUG AT 615' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 423' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4928	4940		
4898	4910		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
OCT 12 2015
KCC DODGE CITY

Signed _____

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

OCT 15 2015

CONSERVATION DIVISION
WICHITA, KS

10/27/15 CKM

10-15-15 Form CP-2/3