

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-03259-00-01  
Spot: NWSWSW Sec/Twnshp/Rge: 23-15S-18W  
995 feet from S Section Line, 4955 feet from E Section Line  
Lease Name: RUDER Well #: 3-23  
County: ELLIS Total Vertical Depth: 3563 feet

Operator License No.: 31225  
Op Name: HADDOCK, JACK L.  
Address: 778 TOULON AVE  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	2728		
PROD	5.625	3558		125 SX
SURF	8.765	205		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/09/2015 1:00 PM  
Plug Co. License No.: 3194 Plug Co. Name: TRI UNITED, INC  
Proposal Rcvd. from: EUGENE LEIKER Company: TRI UNITED, INC Phone: (785) 628-3670

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Poor casing.  
Perforations - 3366' - 3370' LKC 3558' - 3563' ARB  
Well was a wash down.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/09/2015 5:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

C & J perforated at 1750', 1200' and 525'. Tri United ran in hole with tubing to 3400', mixed and pumped 100 sx cement w/200 # hulls mixed in. Pulled tubing to 2500', mixed and pumped 100 sx cement w/150 # hulls mixed in. Pulled tubing to 1100', mixed and pumped 45 sx cement to circulate cement to surface. Pulled tubing. Rigged to 4 1/2" casing and pumped 20 sx cement to pressure with 500 psi. Shut in pressure 500 psi. Rigged to 4 1/2" to 5 1/2" casing with instant pressure at 300 psi. 8 5/8" casing full of cement.

GPS: 38.72869 -099.30023

Perfs:

Top	Bot	Thru	Comments
3558	3563		
3366	3370		

KCC WICHITA  
OCT 26 2015  
RECEIVED

Remarks: GLOBAL CEMENTING TICKET # 2523

Plugged through: TBG

District: 04

Signed [Signature]  
(TECHNICIAN)

10/27/15 CKM

CM

OCT 14 2015