

15-185-00950-0000

1-5-88

To: 1 050982
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15 Drill Completion Date 8/30/54

NE SW NW, SEC. 23, T. 25 S, R. 14 W/EX
3630 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name Tanner Well # 1

Operator: Kelso Casing Pulling, Inc.
Name & Address Box 347
Chase, KS 67524

County Stafford 128.28

Well Total Depth 3947 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 832

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:45 a.m. Day: 5 Month: 1 Year: 19 88

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 3947' PRTD 3878' Perfs at 3846 1/2 - 3856 1/2'

1st plug sand back to 3790' and dump 5 sx cement on top of sand through bailer,

2nd plug pump down 10 3/4" with 4 sx hulls and 200 sx ATL cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:45 p.m. Day: 5 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3790' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down the 10 3/4" with 4 sx hulls and 200 sx ATL cement.

Maximum pressure 800 psi and shut in 500 psi.

Remarks: Used ATL cement by Allied. Recovered 3000' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 1-11-88

Signed Richard W. Lucas
(TECHNICIAN)

INV. NO. 19485
1-5

07 1988 1-7-1988