

1 080373

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,389 - 6D-60

E/2 SE SE, SEC. 12, T 29 S, R 14 W/E

660 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Prather Well # 1

Operator: Berexco, Inc.

County Pratt

Name & Address 970 Fourth Financial Center

Well Total Depth 4608 149,76 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 479

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 10:40 am Day: 10 Month: May Year: 19 85

Plugging proposal received from Bill Fulls

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4602' Perfs at 4328-30 & 4032-36'

1st plug sand back to 3950' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Jack Luthi saw all (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:15 am Day: 10 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3950' and dump 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 300 psi

MAY 21 1985

Remarks: Recovered 3240' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-21-85

INV. NO. 8201

Signed J. A. Luthi (TECHNICIAN)