

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21316-00-00
Spot: CNWNWSE Sec/Twnshp/Rge: 11-29S-14W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: LEE Well Number: 1
County: PRATT Total Vertical Depth: 4698 feet

Operator License No.: 30128
Op Name: WHITE, KENNETH S.
Address: 260 N. ROCK RD. SUITE 240
WICHITA, KS 67206

Conductor Pipe: Size feet: \$152.69
Surface Casing: Size 8.625 feet: 408 WITH 300 SX CMT
Production: Size 4.5 feet: 4698 WITH 195 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/10/2002 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4260' & 4 SX CMT. PLUG AT 820' WITH 15 SX GEL & 50 SX CMT. PLUG AT 430' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/10/2002 2:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 4506-13, 4554-62'. SANDED BACK TO 4260' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 820' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 430' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3020' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
KANSAS CORPORATION COMMISSION

Signed

Stephen J. Pfeifer
(TECHNICIAN)

JAN 16 2002
1-16-2002
CONSERVATION DIVISION

INVOICED
JAN 15 2002
DATE Jan 17, 02
INV. NO. 20020612691P