

To: 1 010120
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,359-DD-DD
NW NE SE, SEC. 24, T 29 S, R 14 W
2310 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9427
Operator: Riseden Ltd./Sharp
Name & Address Engineering Oil Operations
708 One Main Place
Wichita, KS 67202

Lease Name Kerr Well # 1
County Pratt 146.38
Well Total Depth 4504 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 298

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111
Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 1:35 pm Day: 31 Month: March Year: 19 86

Plugging proposal received from Deacon Pulley
(company name) Rockhold (phone) 316-792-2506

were: 5 1/2" at 4503' PBT 4449' Perfs at 4435-40'
1st plug sand back to 4375' and dump 5 sx cement on top of sand through bailer
2nd plug squeeze well with 4 sx hulls, 10 sx gel, 50 sx cement, 5 sx gel and 120 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 pm Day: 31 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4375' and dumped 5 sx cement on top of
sand through bailer. 2nd plug squeezed well with 4 sx hulls, 10 sx gel, 50 sx cement, 5
sx gel and 120 sx cement.

Maximum pressure 450 psi and shut in 375 psi
Remarks: Used Econo-Light cement by Halliburton.
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

INVOICED
DATE APR 8 1986
INV. NO. 13337