

2 010109

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 155-21,065-0000

NENENE, SEC. 3, T 24 S, R. 5 W/EX

4950 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5601

Lease Name Stroud Well # 1

Operator: Associated Petroleum Consultants,
Name & Address Suite 600 - One Main Place
Wichita, Kansas 67202

County Reno 129.03

Well Total Depth 3970 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 680 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Co License Number 5302

Address Wichita, KS

Company to plug at: Hour: 6:00a.m. Day: 26 Month: 8 Year: 19 85

Plugging proposal received from Allen Bates

(company name) Red Tiger Drilling (phone) _____

were: pump 50 sacks to 3970 - pull drill pipe to 730 feet and pump 35 sacks -
spot 35 sacks at 400 feet-bridge at 40 feet and spot 15 sacks to surface.
10 sacks in the rat hole

Plugging Proposal Received by Warren Kirkpatrick
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:15p.m. Day: 26 Month: 8 Year: 19 85

ACTUAL PLUGGING REPORT Pumped 50 sacks of cement to 3970 feet down the drill pipe.

Pulled the drill pipe to 730 feet and pumped 35 sacks. Pulled drill pipe to 400 feet

and spotted 35 sacks of cement. Built solid bridge at 40 feet and spotted 15 sacks of

cement to surface. Spotted 10 sacks of cement in rat hole and 2 sacks in water well.

Remarks: Howco Ticket #099040-7
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

observe STATE CORPORATION COMMISSION

Signed W Kirkpatrick
(TECHNICIAN)

DATE SEP 12 1985

SEP 12 1985

INV. NO. 10040

CONSERVATION DIVISION
Wichita, Kansas

9-12-85

RO

FORM CP-2/3
Rev. 01-84