

7-21

2-070470

279
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-155-21,201-0000

NW NW SE, SECTION 20 TOWNSHIP 24 RANGE 8W

OPERATOR LICENSE # 6120

2310 FEET FROM S SECTION LINE

2310 FEET FROM E SECTION LINE

OPERATOR Cabot Petroleum Corp.

NAME & P. O. Box 9999

ADDRESS Amarillo, TX 79105

LEASE NAME: Rush #1-20

COUNTY: Reno

WELL TOTAL DEPTH: 4230' 137.47

CONDUCTOR PIPE: _____

SURFACE CASING: 214' of 8-5/8"

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: _____

ADDRESS: _____ LICENSE: _____

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 20 MONTH: 7 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: _____

COMPANY NAME: _____ PHONE: _____

WERE: CIBP 3675' & 5 sx - 35 sx @ 1420' - 35 sx @ 420'
264' to 0.

PLUGGING PROPOSAL RECEIVED BY: Dave Wertz

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 11:30 DAY: 21 MONTH: 7 YEAR: 1992

ACTUAL PLUGGING REPORT:

Set CIBP @ 3675' & 5 sx common - shot 5-1/2" csq off
at 3110' - pulled to 1420' - circ hole full of gel &
pumped 35 sx - pulled to 920' - pumped 35 sx - pulled
to 264' & circ to surf.

REMARKS: Hallibu rton #245827 60/40 4%

I DID OBSERVE THIS PLUGGING.

INVOICED

Jack Luthi
Jack Luthi (AGENT)

DATE 8-11-92

WELL NO. 35941

FORM CP-2/3
REV. 3/90

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 28 1992
CONSERVATION DIVISION
WICHITA, KS