

To: 1 090661
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 15-185.00707-0000 Drill completion 3/9/57 201
SW NE SE, SEC. 29, T 25 S, R 14 WEX 12

3-28

1650 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 5010
Operator: Knighton Oil Company, Inc.
Name: 710 Petroleum Building
Address: Wichita, KS 67202

Lease Name English Well # 1
County Stafford
Well Total Depth 4300 139.75 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 287

Abandoned Oil Well Gas Well Input Well SMO Well O&A
Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:30 a.m. Day: 28 Month: 3 Year: 19 96

Plugging proposal received from Ken Gates
(company name) Pratt Well Service, Inc. (phone) 316-672-2531

Work: 5 1/2" at 4299' w/225 sx cement, PBD 4299', Perfs at 3905-15, 3944-56'
1st plug sand back to 3870' and dump 5 sx cement on top of sand through bailer.

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

RECEIVED
IANS
CORP
FORM 1
4-1-1996

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:05 a.m. Day: 28 Month: 3 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3870' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 125 sx cement.

Maximum pressure 100 psi and shut in 0.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (customer) observe this plugging.

DATE 4-10-96

Signed [Signature] (TECHNICIAN)

INV. NO. 45181

3-28 JUN 27 1996