

To: 1 052196
STATE CORPORATION COMMISSION 11-21
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Drilled 10/31/62
C NE SW, SEC. 30, T 25 S, R 14 W
1980 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 31514
Operator: Thoroughbred Associates
Name:
Address 10 Colonial Ct.
Wichita, KS 67207

Lease Name Childs Well # 1
County Stafford 147.71
Well Total Depth 4545 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 292

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 2 p.m. Day: 21 Month: 11 Year: 19 97

Plugging proposal received from Kent Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

logs: 5 1/2" at 4540' w/125 sx cement, PBTD 4456', Perfs at 4232-37'

1st plug sand back to 4180' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:15 p.m. Day: 21 Month: 11 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4180' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released

8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 125 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2156.40' of 5 1/2" casing.

INVOICED DEC 10 1997 (If additional description is necessary, use BACK of this form.)

DATE (did not observe this plugging.)

Signed Richard M. Lacey
(TECHNICIAN)

INV. NO. 49628