

1 040526

3-6

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19- 185-21,948 - 0000

C SW SW, SEC. 31, T. 25 S, R. 14 W/4

660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5893

Lease Name Beck Well # B-1

Operator: Pratt Well Service, Inc.

County Stafford 143.65

Name & Address P.O. Box 847

Well Total Depth 4420 feet

Pratt, KS 67124-0847

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 366

Abandoned Oil Well  Gas Well  Input Well  SHD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 11 a.m. Day: 6 Month: 3 Year: 19 91

Plugging proposal received from Fred Mease

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 4 1/2" at 4420' w/100 sx cement, Perfs at 4284-90'

1st plug sand back to 4234' and dump 4 sx cement on top of sand through bailer or set CIBP with 4 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 13 sx gel, release wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:45 a.m. Day: 6 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4198' and put 4 sx cement on top of plug through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Pumped through 8 5/8" collar welded into 10 3/4" surface pipe.

MAR 11 1991

Maximum pressure 400 psi and shut in 100 psi.

CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2114' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

Wichita, Kansas

INVOICED

(if desired) observe this plugging.

DATE 3-15-91

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 31189