

1 051323

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
300 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-19 15-047-20324-0000  
API NUMBER 15- Docket #D-19,796

NE SW NE, SEC. 5, T 26 S, R 18 W  
3630 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5047  
Operator: Rupe Oil Company  
Name & Address: P.O. Box 2273  
Wichita, KS 67214

Lease Name Dillon Well # 1  
County Edwards 154.47  
Well Total Depth 4753 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 347

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1 p.m. Day: 19 Month: 6 Year: 19 90

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4744' PBSD 4440' Perfs at 4690-96, 4334-40'

1st plug sand back to 4280' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 19 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4280' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2750' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-3-90  
INV. NO. 28524

observe this plugging

JUN 21 1990

CONSERVATION DIVISION  
Wichita, Kansas

Signed Richard W. Lacy (TECHNICIAN)

6-21-1990