

15-047-20609-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Edwards SEC. 9 TWP. 26 RGE. 18w E/W
 Location as in quarters or footage from lines:

SE NW SE

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

Locate Well
 correctly on above
 Section Platt.

Lease Owner John Jay Darrah, Jr.

Lease Name Fatzer #1 Well No. _____

Office Address 405 Century Plaza Bldg., Wichita, Ks. 67202

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 1/17/83

Plugging completed 1/26/83

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom T.D. 4801'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out. |
|-----------|---------|------|----|--------|--------|-------------|
| | | | | 8 5/8 | 346' | none |
| | | | | 4 1/2" | 4750' | 2581' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Plugged bottom with sand to 4635' & ran 4 sacks cement. Shot pipe at
4118', 3386', 3512', 3278', 3066', 2844', & 2581'. Pulled total of 58 joints.
Plugged well with 3 sacks hulls, 20 gel, 70 cement, 20 gel, 1 hull, plug,
and 100 cement.

RECEIVED
 STATE CORPORATION COMMISSION

Plugging complete

JAN 31 1983

CONSERVATION DIVISION

Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of January, 1983



Irene Hoover
 Notary Public.

My Commission expires: _____

DRILLERS LOG

15-047-20609-0000

OPERATOR: Elk River Oil Co.; Suite 300; 200 E. 1st; Wichita, Ks. 67202

CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name Fatzer Well No. 1

Sec. 9 T. 26 R. 18 W Spot SE NW SE

County Edwards State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 346' with 200 Sxs.

Production: _____ @ _____ with _____ Sxs.

Type Well: Oil Total Depth 4801' KB

Drilling Commenced: 12/26/79 Drilling Completed 1/7/80

| Formation | From | To | Tops |
|-------------------|------|------|--------------------|
| Cellar | 0 | 7 | Mississippi - 4679 |
| Sand | 7 | 350 | |
| Clay, Shale | 350 | 658 | |
| Lime | 658 | 672 | |
| Shale | 672 | 1244 | |
| Shale, Lime | 1244 | 1800 | |
| Shale | 1800 | 2250 | |
| Shale, Lime | 2250 | 2689 | |
| Lime | 2689 | 2898 | |
| Lime, Shale | 2898 | 3360 | |
| Lime | 3360 | 3480 | |
| Lime, Sandy shale | 3480 | 3665 | |
| Lime, Shale | 3665 | 4270 | |
| Lime | 4270 | 4405 | |
| Lime, Shale | 4405 | 4620 | |
| Lime | 4620 | 4655 | |
| Lime, Shale | 4655 | 4679 | |
| Lime | 4679 | 4801 | |

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1980

CONSERVATION DIVISION
Wichita, Kansas

Prod. Casing - 4 1/2" 9.5# @ 4750

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

| Formation | Perforated Interval | Number Shots |
|-----------|---------------------|--------------|
| | | |
| | | |
| | | |
| | | |

Initial Production: _____

Electric Log _____ Type and Depths Covered _____