


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail & Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Edwards County, Sec. 11 Twp. 26 Rge. 18W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Hudson Petroleum Co.
Lease Name Newsom Well No. 1
Office Address 1112 S. W. Blvd., Kansas City, Mo.
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed May 29 19 60
Application for plugging approved May 31 19 60
Plugging commenced June 1 19 60
Plugging completed June 10 19 60
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, St. John, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4769 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	321'	NONE
				5 1/2"	4769'	2206'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug at 3320', drove plug to bottom of 3968' run 1/2 ud of sand and 5 gal. rock. mixed and run 5 sacks cement shot casing at 4109'
bailed fluid to 300' set 10' rock bridge mixed and run 20 sacks cement mud to 40' set 10' rock bridge with 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUL 6 1960
CONSERVATION DIVISION
Wichita, Kansas

7-6-1960

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 361, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Roy L. Myers
Roy L. Myers
Box 361, Great Bend, Kansas Sec. Treas.
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of June, 19 60

My commission expires December 18, 1962 Juanita R. Myers Notary Public.



WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-047-00094-0000

Company- HUDSON PETROLEUM CO.
Farm- Newsom No. 1

SEC. 11 T. 26 R.18W
NW NW SE

Total Depth. 4770'
Comm. 5-11-59 Comp. 5-26-59
Shot or Treated.
Contractor. Chief Drlg. Co.
Issued. 4-15-61

County Edwards
KANSAS



CASING:
8 5/8" 299' cem w/225 sx.
5 1/2" 4768' cem w/125 sx.

Elevation. 2160' DF

Production. 10 BOPD

Figures indicate Bottom of Formations

top soil, sand & shale	299
shale & shells	480
sand	490
red bed	560
red bed & sand	580
red bed & shale	590
red bed & shale	1195
Anhydrite	1210
sand	1220
shale & shells	1380
shale	1800
shale w/lime	2305
lime & shale	2425
lime	2790
lime w/shale	3165
shale	3365
shale w/lime strks	3505
lime	3575
shale	3715
shale w/lime	3810
lime	4592
chert	4665
chert & KHS	4685
chert	4765
Viola	4770
Total Depth	

TOPS:	
Anhydrite	1195
Heebner	3910
Toronto	3927
Douglas	3947
Brown Lime	4046
Lansing	4056
Base Kansas City	4418
Cherokee Sand	4550
Mississippi	4576
Kinderhook Shale	4635
Kinderhook Sand	4661
Viola	4733