


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Edwards County, Sec. 11 Twp. 26S Rge. (E) 18 (W)
Location as "NE/CNW/SW" or footage from lines C S/2 NE SE
Lease Owner Gramehart-Miller Oil Company
Lease Name Newsom "B" Well No. 1
Office Address 1005 East Second, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 30, 1954 19
Application for plugging filed December 6, 1954 19
Application for plugging approved December 6, 1954 19
Plugging commenced December 6, 1954 19
Plugging completed December 10, 1954 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives, Pratt Kansas
Producing formation Depth to top Bottom Total Depth of Well 4824 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	291	None
				5 1/2"	4660	4049

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock to 4780', top of cement 4745'.
Filled hole with mud to 320', set rock bridge, dumped 20 sacks cement. Top of cement 270'.
Filled with mud to 35', set rock bridge, ran 10 sacks cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Company (License No. 12)
Address Box 711, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J. A. Gilliland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. A. Gilliland*
1005 East Second, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 1954

Juanita L. Davis
Notary Public.
My commission expires November 5, 1958

PLUGGING
FILE SEC 11 T 26 R 18W
BOOK PAGE 82 LINE 12

15-047-00134-0000

NO. 1 WESSON "B"

WELL RECORD

Location: C S/2 NE 33, 11-263-18W
Edwards County, Kansas

Commenced: October 14, 1954

Operator: Graham-Miller Oil Company
1005 East Second, Wichita, Kansas

Completed: October 29, 1954

Contractor: Graham-Nessman-Rinehart Drilling Co.
1005 East Second, Wichita, Kansas

Elevation: 2165 KB

Productions:

Casing Records: 8 5/8" @ 291' w/250 sacks cement
5 1/2" @ 4660' w/75 sacks cement

.....L O G.....

Sand	102
Sand-clay	225
Gray shale	310
Sandy shale	535
Red bed-shale	1939
Line-shale	4154
Line	4201
Line-shale	4281
Line	4422
Line-shale	4525
Line	4532
Coring	4547
Line-shale	4565
Line	4600
Line-shale	4614
Line	4658
Line-shale	4679
Line-sand	4728
Line-sand	4742
Line-shale	4780
Line-Arbuckle	4824 R.T.D.

Heebner 3871 (-1706)
Brown lime 3998 (-1833)
Lansing 4007 (-1842)
Kinderhook 64 4528 (-2363)
Viola Chert 4569 (-2404)
Viola Dolomite 4617 (-2452)
Simpson 4710 (-2545)
Arbuckle 4801 (-2636)

The undersigned, GRAHAM-NESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-NESSMAN-RINEHART DRILLING COMPANY

By: J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me this 5th day of November, 1954.

F. L. [Signature]
Notary Public

My Commission Expires: June 3, 1958

PLUGGING
WELL SEC 11 T 26 R 18W
BOOK PAGE 82 LINE 12