

WELL PLUGGING RECORD

See All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Edwards County, Sec. 11 Twp. 26S Rge. 18 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines S1/4
Lease Owner Phillips Petroleum Company
Lease Name Fletcher "A" Well No. 1
Office Address Box 779, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 17, 19 51
Application for plugging filed November 19, 19 51
Application for plugging approved November 17, 19 51
Plugging commenced November 17, 19 51
Plugging completed November 18, 19 51
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19 -
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough
Producing formation Arbuckle Depth to top 5088 Bottom 5143 Total Depth of Well 5143 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Dry	5088	5143	8-5/8"	292.17'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole from 5143' to 290'. Set Howco plug at 290'. Dumped 25 sx. cement in filling to 185'. Mudded hole to 35' and dumped 15 sx. cement in filling to base of cellar. Well plugged and abandoned at 2:00 A.M. 11-18-51.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Berwick Drilling Company
Address Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
A. J. Willis (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. J. Willis

Box 779, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of November, 19 51.

My commission expires November 18, 1953

23-8390-s 6-51-20M

PLUGGING
FILE SEC 11 T26 R18 W
BOOK PAGE 125-110613

Joseph W. Beal
Notary Public.

NOV 21 1951

CONSERVATION DIVISION
Wichita, Kansas

11-21-1951

Formation Record

15-047-10090-0000

Lease

Fletcher "A"

Well No. 1

FROM	TO	Formation	REMARKS
0	175	Sand.	
175	500	Shale.	
500	600	Sand and shale.	
600	640	Red Bed.	
640	657	Anhydrite.	
657	800	Red Bed and shells.	
800	1250	Red Bed, shale and shells.	
1250	1850	Shale and shells.	
1850	2000	Shale.	
2000	2475	Lime and shale.	
2475	2550	Lime.	
2550	2590	Cherty lime.	
2590	2685	Lime and shale.	
2685	2815	Broken lime and shale.	
2815	3065	Lime and shale.	
3065	3225	Shale and shells.	
3225	3330	Shale.	
3330	3490	Lime and shale.	
3490	3595	Sandy lime and shale.	
3595	3655	Lime.	
3655	3700	Lime and shale.	
3700	3917	Lime.	
3917	4125	Lime and shale.	
4125	4220	Lime.	
4220	4310	Lime and shale.	
4310	4490	Lime.	
4490	4550	Lime and shale.	
4550	4580	Lime.	
4580	4620	Lime and sand.	
4620	4660	Lime.	
4660	4700	Cherty lime.	
4700	4710	Chert.	
4710	4734	Cherty lime.	
4734	4753	Chert.	
4753	4764	Sandy shale.	
4764	4775	Sand.	
4775	4793	Sandy shale.	
4793	4810	Cherty lime and shale.	
4810	4825	Sand.	
4825	4850	Sandy shale and lime.	
4850	4900	Lime and chert.	
4900	4953	Cherty lime.	
4953	4999	Lime.	
4999	5065	Lime and sand.	
5065	5095	Sandy lime.	
5095	5125	Sand and shale.	
5125	5143	Lime.	

Top Arbuckle 5088'.

PLUGGING
FILE SEC-111-26110
BOOK PAGE 125 LINE 13

NOV 2 1950
COLUMBIA UNIVERSITY
LIBRARY