

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-047-30110-0000
API NUMBER 15-N/A

LEASE NAME Madden

WELL NUMBER 1

1980 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 12 TWP. 26S RGE. 18W (X) or (W)

COUNTY Edwards

Date Well Completed _____

Plugging Commenced 10-22-93

Plugging Completed 10-22-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Pickrell Drilling Company, Inc.

ADDRESS 110 N. Market, Suite 205 Wichita, Kansas 67202

PHONE#(316) 262-8427 OPERATORS LICENSE NO. 5123

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-22-93 (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? Previously mailed

Producing Formation Miss. Depth to Top 4486 Bottom 4537 T.D. 4597

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	294	8 5/8	294	None
		0	4596	5 1/2	4596	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Used 60/40 Poz 8% gel to plug. Through tubing pumped 23 sx of gel mixed w/ water plus 35 sx. cement at 4440. Pulled tubing to 1020 and spotted 95 sx cement, circulated hole. Pulled tubing from hole. Used 10 sx. cement to fill hole. Pumped 140 sx cement down annulus between 5 1/2 and 8 5/8. Shut in at -0- lbs. Did not go on vacuum. Witnessed by Richard Lacy.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing, Inc. License No. _____

Address P.O. Box 31, Russell, Kansas 67665-0031

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss. Wichita, Kansas

Jack Gurley (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: that he has knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack Gurley

(Address) 110 N. Market Suite 205 Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 29th day of October, 19 93



Karen A. Mans Notary Public