


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plot

Stafford County, Sec. 27 Twp. 25S Rge. 14 W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE NW SW
Lease Owner Wayne Kirkman
Lease Name Wiles Well No. I
Office Address 434 North Market, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) gas
Date well completed 3-20 19 75
Application for plugging filed 8-9 19 76
Application for plugging approved 8-9 19 76
Plugging commenced 8-9 19 76
Plugging completed 8-20 19 76
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2879'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		1735'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

*Rough Plug to 2025' Made
10 ft of sand & dumped 4 cu yd
dumped 2 cu yd filler 10 cu yd
10 cu yd cement with Admix
Cementing Co.
Pump pressure 200 lbs.*

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Inc.
Address 2809 King St. Hutchinson, Kansas

STATE OF kansas COUNTY OF Reno ss.
Art Lamb

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 King St. Hutchinson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of August, 19 76

My commission expires December 31, 1977

[Signature]
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

AUG 25 1976

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

WILES #1

CASING RECORD:

8 5/8" set at 236'
w/200 sacks cement

TOTAL DEPTH:

2879'

OPERATOR:

Wayne L. Kirkman

CONTRACTOR:

Search Drilling Co.

COMMENCED:

March 13, 1975

COMPLETED:

March 20, 1975

DESCRIPTION:

100' N of SE NW SW
Section 27-25S-14W
Stafford County,
Kansas

FORMATION

FROM

TO

REMARKS

Sand	0	100
Sand	100	200
Shale	200	238
Shale	238	535
Shale and Sand	535	821
Shale	821	870
Cement	625	821
Shale	870	1260
Shale	1260	1514
Cement	690	720
Shale	1514	1850
Shale	1850	2015
Lime	2015	2038
Lime	2038	2057
Lime	2057	2135
Shale and Lime	2135	2230
Lime	2230	2377
Shale and Lime	2377	2504
Shale and Lime	2504	2670
Shale and Lime	2670	2775
Lime and Shale	2775	2879
Total Depth	2879	

Logged rand 86 joints
new 4 1/2" casing -
cemented with 300 sack
60-40 posmix-10% salt
preceded by 20 barrels
salt flush by Allied
Cementing Co. plug
down at 1:00 A.M.

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1976

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of knowledge.

SEARCH DRILLING COMPANY

M. A. Dressen

Subscribed and sworn to before me this 21st day of March, 1975.

My commission expires:
August 5, 1975

Virginia S. Fabian
Notary Public

