


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 28 Twp. 25S Rge. 14W (E) (W)
Location as "NE/CNWxSWx" or footage from lines NW NW SW
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name NELLIE WATERS Well No. A
Office Address 800 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed April 4, 1957 19__
Application for plugging filed June 13, 1958 19__
Application for plugging approved June 13, 1958 19__
Plugging commenced June 13, 1958 19__
Plugging completed June 18, 1958 19__
Reason for abandonment of well or producing formation non-productive in commercial quantities
If a producing well is abandoned, date of last production December 21 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Lansing Depth to top 3767 Bottom 4060 Total Depth of Well 4070 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
				8 5/8	286'	Cemented
				5 1/2"	4070'	2921.74

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3890 feet - dumped 5 sacks cement - mudded hole to 240 feet - set 10' rock bridge - dumped 2 sacks Cal Seal and 1 sack cement on rock bridge - waited for Cal Seal to set bailed fluid out of hole waited to see if fluid came back in no fluid return - dumped 30 sacks cement - mudded to 40' set rock bridge - dumped 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company
Address Box 569, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dwight J. Wilson
800 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of July, 19 58

My commission expires August 10, 1961

RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

PLUGGING
FILE SEC 28 T. 25 R. 14W
BOOK PAGE 108 LINE 12

JUL 19 1958

CONSERVATION DIVISION
Wichita, Kansas.

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: March 23, 1957

Contractor: Quaker Drilling Co., Inc.

Completed: April 4, 1957

Nellie Waters "A" No. 1
NW NW SW Sec. 28-25S-14W
Stafford County, Kansas

Elevation: 2000 K. B.

Casing Record:

Set 8 5/8 inch casing at 286 feet with 250 sacks pozmix
Set 5 1/2 inch casing at 4070 feet with 225 sacks pozmix

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Sand	228	Anhydrite	897
Shale and Shells	286	Heebner	3583 -1583
Red Bed and Shale	897	Brown Lime	3741 -1741
Anhydrite	926	Lansing	3767 -1767
Shale and Shells	1915	Base of Kansas City	4060 -2060
Lime and Shale	2195	Rotary Total Depth	4070 -2070
Sandy Lime and Shale	2290		
Lime and Shale	2471		
Shale and Shells	2585		
Lime and Shale	2850		
Shale and Lime	2970		
Lime and Shale	3400		
Sandy Lime & Shale	3460		
Lime and Shale	3875		
Shale and Lime	3930		
Lime	3974		
Shale and Lime	4010		
Lime and Shale	4070		

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the NW NW SW of Section 28, Township 25 South, Range 14 West, Stafford County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. McCaul
Thomas M. McCaul, President

SUBSCRIBED AND SWORN TO before me a Notary Public this 11th day of April, 1957.

Virginia Mandell
Virginia Mandell, Notary Public

MY COMMISSION EXPIRES:
August 10, 1957

PLUGGING
FILE SEC. 28 T. 25 R. 14W
BOOK PAGE 102 LINE 12

RECEIVED
STATE CORPORATION COMM'
JUL 19 1958
CONSERVATION DIVISION
Wichita, Kansas