

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-185-00707-0000

API NUMBER 3/09/57

LEASE NAME English

WELL NUMBER 1

1650 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 29 TWP. 25S RGE. 14 (R) or (W)

COUNTY Stafford

Date Well Completed 3/09/57

Plugging Commenced 3/25/96

Plugging Completed 3/28/96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KNIGHTON OIL COMPANY, INC.

ADDRESS 221 South Broadway-Suite 710, Wichita, Kansas 67202

PHONE#(316) 264-7918 OPERATORS LICENSE NO. 5010

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/27/96 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Lansing/Kansas City Depth to Top 3764 Bottom 4060 T.D. 4299

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|---------|------|--------|--------|------------|
| | | Surface | 287 | 8-5/8" | 287 | None |
| | | Surface | 4299 | 5 1/2" | 4299 | 2200' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pumped 400 lbs. hulls, 10 sacks gel, and 50 sacks cement (60/40 Poz, 6% gel). Mixed and pumped 10 sacks gel and 100 lbs. hulls. Mixed and pumped 125 sacks cement (60/40 Poz, 6% gel) to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service License No. 5893

Address P. O. Box 847, Pratt, Kansas 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Knighton Oil Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Earl M. Knighton, Jr. (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
statements, and matters herein contained and the log of the above-described well as filed th
the same are true and correct, so help me God.

(Signature) Earl M. Knighton, Jr.

(Address) 710 Petroleum Building
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 17th day of April, 19 96

My Commission Expires: 12/11/97

Notary Public
Sarah A. Simon

