

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 30 Twp. 25 Rge. 14W (E) (W)

Location as "NE/CNW/SW" or footage from lines
Tomlinson-Kathol, Inc.

Lease Owner Tomlinson-Kathol, Inc.
Lease Name Beck Well No. 1

Office Address 1125 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A.

Date well completed 3/26 19 63

Application for plugging filed 3/26 19 63

Application for plugging approved 3/26 19 63

Plugging commenced 3/26 19 63

Plugging completed 3/26 19 63

Reason for abandonment of well or producing formation No commercial quantities
of oil or gas encountered

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Elwing

Producing formation None Depth to top Bottom Total Depth of Well 437 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Water			8-5/8"	279'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud was put into the hole to a depth of 270 feet where the bottom plug was set and cemented with 25 sack cement. Mud was again put into the hole to a depth of 40 feet where the top plug was set and cemented with 15 sacks cement. Surface casing was cut off below ground level and the location abandoned.

RECEIVED
STATE CORPORATION COMMISSION

APR 4 1963

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Tomlinson-Kathol, Inc.
Address 1125 Wichita Plaza, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Richard C. Davis (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] 1125 Wichita Plaza, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 28th day of March, 1963

[Signature]

My commission expires 1/19/65

Notary Public.



DRILLERS LOG
 TOMLINSON-KATHOL, INC. ETAL
 # 1 BECK
 C SW NE, SEC. 30-25S-14W
 STAFFORD COUNTY, KANSAS

Contractor - Tomlinson-Kathol, Inc.

Commenced: 3/14/63
 Completed: 3/26/63
 Elevation: 2002 KB

<u>From</u>	<u>To</u>	<u>Remarks</u>
0	200	Sand & Shale
200	250	Clay -Shale
250	934	Shale 279' 8-5/8" Surf. Csg. w/225 sacks cement
934	960	Anhydrite
960	1860	Shale
1860	2045	Shale - Lime
2045	2156	Shale & Lime & Sand
2156	2338	Lime-Shale, Sand streaks
2338	2606	Lime & Shale
2606	2752	Shale - Lime streaks
2752	3221	Lime - Shale
3221	3405	Shale & Lime
3405	3493	Shale & Chalk & Lime
3493	3609	Lime - Shale
3609	3765	Shale & Lime
3765	4218	Lime
4218	4246	Mississippian
4246	4255	Conglomerate
4255	4275	Shale
4275	4313	Shale - Lime
43113	4317	Shale
4317		Rotary Total Depth

	Heebner Shale 3627
	Toronto Limestone 3650
	Douglas Shale 3670
	Brown Lime 3780
	Lansing 3805
	B. K.C. 4086
	Cong. Chert 4231
	Miss. ---
	Kinderhook shale 4234
	Viola 4294

RECEIVED
 STATE CORPORATION COMMISSION

APR 4 1963

CONSERVATION DIVISION
 Wichita, Kansas

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.

Warren E. Tomlinson
 Warren E. Tomlinson

STATE OF KANSAS

SS

COUNTY OF SEDGWICK

Subscribed and sworn to before me this 28th day of March 1963.

Esther Lamore
 Notary Public

My Commission Expires: 1/19/65