

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-21,948-0000

LEASE NAME BECK

WELL NUMBER B-1

660 Ft. from N. Section Line

4620 Ft. from W Section Line

C SW SW
 SEC. 31 TWP. 25 RGE. 14 ~~W~~ or (W)

COUNTY PRAATT

Date Well Completed _____

Plugging Commenced 2-26-91

Plugging Completed 3-6-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR PRAATT WELL SERVICE, INC.

ADDRESS P O BOX 847 PRAATT, KS. 67124

PHONE# (316) 672-2531 OPERATORS LICENSE NO. 5893

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on MARCH 1, 1991 (date)

by STEVE DURANT (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 4420

Show depth and thickness of all water, oil and gas formations. PERFS: 4284-4290, 4 s p f.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
		0	366	10 3/4	366	0
		0	4420	4 1/2	4420	2114'

MAR 14 1991

CONSERVATION DIVISION
 WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
2-28-91: SET CIBP AT 4198, DUMPED FOUR SX CEMENT, CUT & PULLED 2114 FT. OF 4 1/2 CSG, 52 JTS.
3-6-91: TOP HOLE PLUG: 300# HULLS, 10 GEL, 50 SX CEMENT, 10 GEL, 100# HULLS, 150 SX CEMENT, 400# MAX PRESSURE, 100# ISIP. 11:45 A.M.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRAATT WELL SERVICE, INC. License No. 5893

Address NORTH HIGHWAY 61 PRAATT, KS. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PRAATT WELL SERVICE, INC.

STATE OF KANSAS COUNTY OF PRAATT, ss.


JUDY BERRY

PLUGGING CONTRACTOR

(Employee of ~~XXXXXX~~)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) P.O. Pratt, Inc.



SUBSCRIBED AND SWORN TO before me this 13th day of March, 19 91

Dorothy M. Ferguson
 Notary Public

My Commission Expires: Feb. 6, 1993