


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 32 Twp. 25s Rge. 14 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines: NW NW SE



Locate well correctly on above
Section Plot

Lease Owner Inca Oil Company
Lease Name Gerald Goodman Well No. 1
Office Address 234 Mayo Bldg., Tulsa, Ok. 74103
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed June 9, 1977
Application for plugging filed Aug. 8, 1977
Application for plugging approved 19
Plugging commenced May 28, 1977
Plugging completed June 9, 1977

Reason for abandonment of well or producing formation
No Structural Position & Lack of any good show of Oil or Gas
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott, Ks. Corp. Comm.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3984
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Stone Corral		928	+1078			
B/Stone Corral		941	+1065			
Herrington		2028	- 22			
Krider		2066	- 60			
Winfield		2120	- 114			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from 250 feet to 410 feet for each plug set.

3984' Lime - Mud - 9.4, Vis. 40, WL - 8cc, Spot Cement plugs 40 sacks, 250 to 410 - 10 sacks surface to 40' (3 A.M.)

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1977

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Co. CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Stafford, ss.
(employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Herman Sings
P. O. Box 52069, Tulsa, Ok. 74152
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of August, 1977

Ruth Mary Kulin
Notary Public.
My commission expires Dec. 1, 1979

KB LOG TOPS:
 STONE CORRAL 928 + 1078
 B/STONE CORRAL 941 + 1065
 HERINGTON 2028 - 22
 KRIDER 2066 - 60
 WINFIELD 2120 - 114
 TOWANDA 2181 - 175
 FORT RILEY 2214 - 208
 FLORENCE FLINT 2280 - 274
 B/FLORENCE FLINT 2348 - 342
 WREFORD 2348 - 342
 COUNCIL GROVE 2406 - 400
 COTTONWOOD 2531 - 525
 NEVA 2588 - 582
 RED EAGLE 2687 - 681
 (CON'T FOR TOPS)

 Petroleum Information
COMPANIES
 * Copyrighted 1977. Reproduction Prohibited

WABAUNSEE 2856 - 850
 STOTLER 2918 - 912
 TARKIO SD 2981 - 975
 ELMONT 3034 - 1028
 BERN 3118 - 1112
 HOWARD 3183 - 1177
 HEEBNER 3612 - 1606
 TORONTO 3630 - 1624
 DOUGLAS 3650 - 1644
 BROWN LM 3769 - 1763
 LANSING KANSAS CITY
 3791 - 1785
 RTD 3984 - 1978
 TD IN LANSING KANSAS CITY

COMP ISSUED 7-25-77

