

1060172

To: STATE CORPORATION COMMISSION 20 N of E/2 E/2 NW
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,076A00-0
SEC. 33, T 26 S, R 18 W/8X

1300 feet from N/8X section line

2310 feet from W/8X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Sturgeon "A" Well # 1

Operator: TXO Production Corp.

County Edwards

Name & Address 200 West Douglas, Suite 300

Well Total Depth 2306 74.94 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 292

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor FWA Drilling Co., Inc. License Number 6165

Address P. O. Box 970, Yukon, OK 73099

Company to plug at: Hour: 3:00 pm Day: 20 Month: February Year: 19 84

Plugging proposal received from Gerald Veatch

(company name) TXO (phone) 316-265-9441

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 992' with 50 sx cement

2nd plug at 558 with 70 sx cement
solid bridge

3rd plug hulls - plug at 40 -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

6th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X _____ None _____

Operations Completed: Hour: 7:00 pm Day: 20 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 992' with 50 sx cement, 2nd plug at 558' with 70 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rathole with 15 sx cement, 6th plug to circulate

mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
2-22-84
FEB 22 1984

Don Ubel gave the orders and Paul Luthi observed part of the operation.

Remarks: Use 60/40 Pozmix 2% gel 3% cc. by Dowell CONSERVATION DIVISION

(If additional description is necessary, use BACK of this form, Wichita, Kansas)

(old / ~~XXXXXX~~) observe this plugging.

INVOICED

Signed Paul A. Luthi (TECHNICIAN)

DATE 2-24-84

4-MV. NO. 0368

2-20