

To: 1 120099
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Operator: Beren Corporation
Name & Address: Box 723
Hays, KS 67601

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor: Kelso Casing Pulling License Number 6050

Address: Box 176, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 14 Month: 6 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4722' cemented with 150 sx cement Open hole Previously squeezed at 2843-58'
1st plug sand back to 4150' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, release 8 5/8" wiper plug
and pump 125 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3 p.m. Day: 14 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4150' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2000' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED Observe this plugging.

DATE 7-13-88

INV. NO. 21300

6-14-88 6-047-20069-0000 145 R

API NUMBER 15-Drill Completion Date 3/12/70

NE NW SE, SEC. 33, T 26 S, R 18 W

2310 feet from S section line

1650 feet from E section line

Lease Name Welsch Well # 2

County Edwards 155.12

Well Total Depth 4773 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 284

STATE CORPORATION COMMISSION

6-24-88 JUN 24 1988

CONSERVATION DIVISION KANSAS

Signed Dan Goodrow (TECHNICIAN)