

1090976

TO: STATE CORPORATION COMMISSION 12-1 API NUMBER 15-047-21,437-0000  
APP. NW NE SE SEC. 33, T 26 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 2290 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 930 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME GAMBLE WELL # 1-33

TECHNICIAN'S PLUGGING REPORT COUNTY EDWARDS 109, 73

OPERATOR LICENSE # 5004 WELL TOTAL DEPTH 3364 FEET

OPERATOR: VINCENT OIL CORPORATION PRODUCTION CSG: SIZE        FEET

NAME AND 125 N MARKET, SUITE 1075 SURFACE CASING: SIZE 8 5/8" FEET 325'

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL        GAS WELL        INPUT WELL        SWD WELL        D/A X

OTHER WELL AS HEREINAFTER INDICATED       

PLUGGING CONTRACTOR MALLARD JV INC LICENSE NUMBER 4958

ADDRESS P.O. BOX 1009 McPHERSON, KS 67460-1009

COMPANY TO PLUG AT: HOUR: 11:50 PM DAY: 30 MONTH: 11 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM DON

(COMPANY NAME) MALLARD JV INC (PHONE) 316-241-4640

WERE:       

1ST PLUG AT 1100' WITH 40 SX CEMENT, 2ND PLUG AT 350' WITH 50 SX CEMENT,

3RD PLUG AT 40' WITH 10 SX CEMENT,

4TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

5TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT

       PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL        PART        NONE X

OPERATIONS COMPLETED: HOUR: 1:20 AM DAY: 01 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1100' WITH 40 SX CEMENT, 2ND PLUG AT 350' WITH 50 SX CEMENT,

3RD PLUG AT 40' WITH 10 SX CEMENT,

4TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,

5TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID OBSERVE THIS PLUGGING.

SIGNED [Signature]  
(TECHNICIAN) FORM CP-2/3

RECEIVED  
CONSERVATION DIVISION  
WICHITA, KANSAS  
DEC 11 1998  
12-14-98

DEC 16 1998

60449

RAWZ