

1030201

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,040-APD-01
C SW SE, SEC. 15, T 26 S, R 19 WEX

TECHNICIAN'S PLUGGING REPORT

660 feet from ~~W/S~~ section line

660 feet from W/~~EX~~ section line

Operator License # 6668

Lease Name Craft Well # 1

Operator: Theodore I. Leben & Asso.

County Edwards

Name & Address 105 S. Broadway, Suite 640

Well Total Depth 4789 155.64 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Leben Drilling Company License Number 5888

Address 105 South Braadway, Suite 640, Wichita, KS 67202

Company to plug at: Hour: 2:00 am Day: 13 Month: June Year: 19 84

Plugging proposal received from Charles Sharp

(company name) Leben (phone) 316-264-2375

were: PBTD 4205' 4 1/2 set at 4788' Perfs 4172-4176 DV at 590' CIBP at 4205'
Displaced through tubing

1st plug at 4100' with 10 sx cement

Fill hole with 19 sx gel mud to 1200'

2nd plug at 1200' with 20 sx cement

Fill hole with gel mud

3rd plug at 600 with 20 sx cement. Circulate cement to surface.

Plugging Proposal Received by Steve Quenert
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 7:45 pm Day: 13 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4788' PBTD 4205' Perfs 4172-4176 DV at 590' CIBP at 4205'

1st plug at 4100' with 10 sx cement, fill hole with 19 sx gel mud to 1200' and set 2nd

plug at 1200' with 20 sx cement, fill hole with gel mud and set 3rd plug at 600' with

20 sx cement. Circulated cement to surface.

RECEIVED
STATE CORPORATION COMMISSION

JUN 18 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

I (did / ~~xxxxxx~~) observe this plugging.

INVOICED

DATE 7-3-84

Signed Steve Quenert
(TECHNICIAN)

INV. NO. 2262 JUL 24 1984

6-13