

2-100661

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-155-21,148-0000

SW, SECTION 9 TOWNSHIP 24 RANGE 8W

OPERATOR LICENSE # 5585 1892 FEET FROM S SECTION LINE
4950 FEET FROM E SECTION LINE

OPERATOR Clinton Production, Inc.
NAME & 330 N. Armour
ADDRESS Wichita, KS 67206

LEASE NAME: Bachus #1

COUNTY: Reno

WELL TOTAL DEPTH: 4115' 133.73

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 258'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SMD _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: White & Ellis Drilling, Inc.

ADDRESS: _____ LICENSE: 5420

COMPANY TO PLUG AT: HOUR: 12:00a DAY: 12 MONTH: 11 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Floss

COMPANY NAME: White & Ellis Drilling PHONE: _____

WERE: 35 sx @ Arb - 35 sx @ 1450' - 35 sx @ 900' - 35 sx @ 300' - 25 sx @ 60' - 15 sx RH - 5 sx WW

PLUGGING PROPOSAL RECEIVED BY: Don Thompson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE (X)

COMPLETED: HOUR: 12:30a DAY: 12 MONTH: 11 YEAR: 1990

ACTUAL PLUGGING REPORT:

Spotted 35 sx cmt top Arb at 4100' - pulled pipe to 1450' and spotted 35 sx cmt - pulled pipe to 900' and spotted 35 sx cmt - pulled pipe to 300' and spotted 35 sx cmt - pulled pipe to 60' - push plug - circ to 0 w/25 sx cmt - put 15 sx in rat hole and 5 sx in water well.

REMARKS: Howco #058883 60/40 4%

INVOICED

DATE 1-4-91

INV. NO. 30315

John Sanders
John Sanders (AGENT)

RECEIVED
STATE CORPORATION COMMISSION

DEC 19 1990

CONSERVATION DIVISION
FORM 3790sas
REV. 3/90sas

DW