

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

10-17

API NUMBER: 15-155-20,142-10001

C NE SW, SECTION 11 TOWNSHIP 26 RANGE 9W

OPERATOR LICENSE # <u>31191</u>	<u>1980</u>	FEET FROM S SECTION LINE
OPERATOR <u>R &amp; B OIL &amp; GAS INC.</u>	<u>3450</u>	FEET FROM E SECTION LINE
NAME & <u>904 NORTH LOGAN</u>		
ADDRESS <u>ATTICA, KS 67009</u>		
	LEASE NAME: <u>REESE "A" #2</u>	
	COUNTY: <u>RENO</u>	
	WELL TOTAL DEPTH: <u>PBTD 2560'</u>	<u>3214'</u>
	PIPE: <u>4 1/2" @ 2488'</u>	
	SURFACE CASING: <u>8 5/8" @ 286'</u>	

104.45

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL X INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE  
ADDRESS: 127 EAST B, ATTICA, KS 67009 LICENSE: 30346

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 17 MONTH: 10 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: MR. CAPPS

COMPANY NAME: SHAWNEE WELL SERVICE PHONE: (316) 254-7893

WERE: SET CIBP AT 2050' AND 4 SACKS OF COMMON  
35 SACKS AT 1300'  
35 SACKS AT 800'  
330' TO 0'

RECEIVED  
KANSAS CORPORATION COMMISSION  
NOV 04 1996

PLUGGING PROPOSAL RECEIVED BY: J.L.

CONSERVATION DIVISION  
WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART {      } NONE (      )

COMPLETED: HOUR: 4:00 DAY: 17 MONTH: 10 YEAR: 1996

ACTUAL PLUGGING REPORT: SET CIBP AT 2050' AND 4 SACKS OF COMMON. SHOT 4 1/2" CASING OFF AT 1513'. PULLED TO 1300', PUMPED 35 SACKS. PULLED TO 900', PUMPED 35 SACKS. PULLED TO 330' AND CIRCULATED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ALLIED #4174

INVOICED

DATE NOV 06 1996  
INV. NO. 46913

I DID OBSERVE THIS PLUGGING.

Jack Luthi  
JACK LUTHI