

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-21843-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 17-13S-21W
4290 feet from S Section Line, 2310 feet from E Section Line
Lease Name: REED Well #: 1
County: TREGO Total Vertical Depth: 4040 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 4039 | | 125 sx |
| SURF | 8.625 | 260 | | 160 sx |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/21/2015 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: _____ Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered 340 sx 60/40 pozmix 4% gel cement w/800 # hulls and 12 sx gel. DV Tool at 1600' w/400 sx cement. Perforations: 3862' - 3870', 3875' - 3878', 3906' - 3914'. Plugging contractor, Quality Well Service informed that backside was full of cement. Unwitnessed due to steel floor over well head.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/21/2015 1:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report: _____ Perfs: _____

Ran tubing to 3854' and pumped 12 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 2350' and pumped 120 sx cement w/300 # hulls. Pulled tubing to 1200' and pumped 145 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 20 sx cement. Backside has cement to surface.


GPS: 38.92627 -099.6775

Remarks: QUALITY WELL SERVICE TICKET # 6122 REED FEE FUND PROJECT CONTROL # 20140096-001

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

KCC WICHITA

NOV 16 2015

RECEIVED