

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-023-20356-00-00
Spot: SESWNENW Sec/Twnshp/Rge: 23-2S-42W
1130 feet from N Section Line, 1830 feet from W Section Line
Lease Name: RATH Well #: 2
County: CHEYENNE Total Vertical Depth: 1835 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1832		125 SX
SURF	8.625	361		210 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/27/2015 12:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix 4% gel cement w/200 # hulls.
8 5/8" surface casing set at 361' w/210 sx cement.
4 1/2" production casing set at 1832' w/125 sx cement.
TD 1835', PBSD 1800'
Perforations: 1636' - 1656'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/27/2015 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 1555' and pumped 140 sx cement w/200 # hulls. CWC. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 125 sx cement. 8 5/8" annulus began flowing due to casing leak below 8 5/8" casing. Shut in 4 1/2" casing. Connected to 8 5/8" surface casing and pumped 40 sx cement at 200 psi. Both casings full and stationary.

GPS: 39.86937N -102.00528W

Perfs:

Top	Bot	Thru	Comments
1636	1656		

Remarks: AMERICAN WARRIOR INC. SERVICE RIG. SWIFT SERVICES TICKET # 28997

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

KCC WICHITA

NOV 16 2015

RECEIVED

OCT 29 2015