

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-21776-00-00
Spot: SWNESWSW Sec/Twnshp/Rge: 3-27S-12W
985 feet from S Section Line, 4414 feet from E Section Line
Lease Name: STUDER Well #: #2-1
County: PRATT Total Vertical Depth: 4312 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4311	1886	WITH 100 SX CMT
SURF	8.625	285		WITH 140 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2015 2:00 PM
Plug Co. License No.: 30481 Plug Co. Name: APOLLO ENERGIES, INC.
Proposal Rcvd. from: JIM BYERS Company: APOLLO ENERGIES, INC. Phone: (620) 672-9001

Proposed Plugging Method: SAND BACK 50' ABOVE PERFS & 4 SX CMT. PLUG AT 650' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 30' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/21/2015 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4165' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 658' WITH 10 SX GEL & 50 SX CMT. HAD NO RETURNS. 2ND PLUG AT 314' WITH 50 SX CMT. HAD NO RETURNS. SDON TO LET CEMENT SET. 10/21/15: TAG TOC WITH TBG AT 640'. SPOT 50 SX CMT AT 640'. SPOT 50 SX CMT AT 314'. SPOT 20 SX CMT AT 64'. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4231	4250		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

SA

KCC WICHITA

NOV 12 2015

RECEIVED

RECEIVED
NOV - 4 2015
KCC DODGE CITY