

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-115-20748-00-00  
Spot: NENWNE Sec/Twnshp/Rge: 24-21S-4E  
4988 feet from S Section Line, 1785 feet from E Section Line  
Lease Name: ALLISON Well #: 3  
County: MARION Total Vertical Depth: 2714 feet

Operator License No.: 5920  
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G  
Address: PO BOX 522  
CANTON, KS 67428

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 4.5   | 2604       |             | 125 SX   |
| SURF   | 8.625 | 200        |             | 125 SX   |

Well Type: SWD UIC Docket No: D21073.0 Date/Time to Plug: 09/18/2015 12:00 AM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: TERRY P BANDY Company: Phone: (620) 628-4428

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: HUNTER CLARK WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/25/2015 12:00 PM KCC Agent: HUNTER CLARK

Actual Plugging Report:

Perfs:

BUD PULLED ONLY 1900' OF TUBING OUT OF WELL. FISHED OUT ALL TUBING. SAND @ 2464' 4 SXS CAP. RAN 2 3/8" TO 300' PUMPED 45 SKS 60/40/4%. RAN 1" TO 45' HIT CEMENT PUMPED 15 SKS 60/40/4% TOP OFF WITH 10 SKS. DID CIRCULATE 0'. STAYED FULL.

KCC WICHITA  
NOV 09 2015  
RECEIVED

Remarks: TICKET #48385 CONSOLIDATED EL DORADO

Plugged through: TBG

District: 02

Signed [Signature]  
(TECHNICIAN)

JK

UIC