

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-145-21398-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 25-20S-19W  
920 feet from S Section Line, 1400 feet from E Section Line  
Lease Name: MECKFESSEL Well #: 25-15  
County: PAWNEE Total Vertical Depth: 2450 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2448	0	WITH 150 SX CMT
SURF	8.625	393		WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/03/2015 9:00 AM  
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.  
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: LOAD & PRESSURE UP ON 4 1/2". IF HOLDS PERFORATE AT 1275' SQUEEZE WITH 50 SX CMT. LET CMT SET & TAG. PERFORATE AT 450' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/03/2015 11:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

LOAD 4 1/2" CASING. PRESSURED TO 700 PSI & HELD. PERFORATE AT 1278'. BEGAN PUMPING CMT & LOST CIRCULATION AT 100 SX CMT. BEAR PETROLEUM WANTED TO KEEP PUMPING. IMMEDIATELY REGAINED CIRCULATION. CMT TO SURFACE WITH 450 SX CMT TOTAL.

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

RECEIVED  
NOV - 4 2015  
KCC DODGE CITY

Signed

Larry Harris ECRS

(TECHNICIAN)  
KCC WICHITA

NOV 12 2015

RECEIVED