

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-01657-00-00
Spot: NWNWNESE Sec/Twnshp/Rge: 35-21S-12W
2440 feet from S Section Line, 1000 feet from E Section Line
Lease Name: TEICHMANN Well #: 1
County: STAFFORD Total Vertical Depth: 3658 feet

Operator License No.: 30765
Op Name: BLAZER, JAMES E. DBA J.R. OIL PROD
Address: 815 4TH ST
NATOMA, KS 67651

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|-----------------|
| PROD | 5.5 | 3650 | 0 | WITH 150 SX CMT |
| SURF | 10 | 190 | | WITH 175 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2015 12:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK TO 3300' WITH 5 SX CMT. PERFORATE AT 630' WITH 25 SX CMT & 100# HULLS. PERFORATE AT 230'. CIRCULATE TO SURFACE INSIDE & OUT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: NONE
Date/Time Plugging Completed: 10/19/2015 3:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

SANDED BACK TO 3300' WITH 5 SX CMT. PERFORATE AT 640' & 230'. RUN TBG TO 630' & PUMPED 50 SX CMT & 200# HULLS (25 SX CMT INSIDE & 25 SX CMT OUTSIDE OF CASING). LET SIT FOR 1 1/2 HOURS. DIDN'T TAG CMT. RAN TBG TO 630' AGAIN & PUMPED 150 SX CMT & 200# HULLS. CMT CIRCULATED TO SURFACE INSIDE & OUT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3408 | 3411 | | |
| 3395 | 3398 | | |
| 3360 | 3370 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

District: 01

Signed [Signature]
517 (TECHNICIAN)

RECEIVED
NOV - 4 2015
KCC DODGE CITY

KCC WICHITA
NOV 12 2015
RECEIVED