

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-20327-00-01
Spot: SENW Sec/Twnshp/Rge: 10-5S-33W
3300 feet from S Section Line, 3300 feet from E Section Line
Lease Name: CURTIN Well #: 1
County: RAWLINS Total Vertical Depth: 4485 feet

Operator License No.: 33263
Op Name: BOWMAN, WILLIAM F. DBA THE BILL
Address: 2640 WRD
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4483		
SURF	8.625	287		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/21/2015 8:30 AM
Plug Co. License No.: 33755 Plug Co. Name: QUALITY PLUS OILFIELD SERVICES, LLC
Proposal Rcvd. from: BILL BOWMAN Company: THE BILL BOWMAN OIL CO. Phone: (785) 259-1297

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/300 # hulls.
8 5/8" surface pipe pre-set at 287' w/225 sx cement.
5 1/2" production casing set at 4483' w/175 sx cement.
DV Tool set at 2740' w/350 sx cement. TD 4485'.
Perforations: 4406' - 4410', 4216' - 4219', 4008' - 4012' and 3990' - 3994'.
Well is non-commercial.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/21/2015 12:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4300' and pumped 1000 # gel followed by 75 sx cement w/300 # hulls. Pulled tubing to 2780' and pumped 135 sx cement w/200 # hulls. Pulled tubing to 1368' and pumped 140 sx cement. CWC. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 25 sx cement. Casing full. Connected to 8 5/8" surface casing with immediate pressure to 300 psi.

GPS: 39.63497N -101.01284W

Perfs:

Remarks: QUALITY PLUS OILFIELD SERVICES LLC SERVICE UNIT AND CONSOLIDATED OILWELL SERVICES
TICKET # 49601

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

cm

OCT 29 2015

KCC WICHITA

NOV 16 2015

RECEIVED

Form CP-2/3