

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-20502-00-00  
Spot: NESE Sec/Twnshp/Rge: 4-31S-9W  
1980 feet from S Section Line, 660 feet from E Section Line  
Lease Name: WINGATE A Well #: 2-4  
County: HARPER Total Vertical Depth: 4534 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4534	3068	125 SX
SURF	8.625	259		225 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/05/2015 12:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/08/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP @ 4410' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 3068' PULLED CASING. RAN TUBING INTO 1531' LOADED HOLE WITH 300 LBS OF MUD, SPOTTED 35 SX OF CEMENT AND 50 LBS OF HULLS. PULLED TUBING TO 1011' SPOTTED 35 SX OF CEMENT. PULLED TUBING TO 306' CIRCULATED TO SURFACE WITH 115 SX OF CEMENT. CEMENT FELL BACK TOPPED OFF WITH 15 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
4460	4476		

**KCC WICHITA**  
**NOV 17 2015**  
**RECEIVED**

Remarks: CEMENT ALLIED. DENIED TA LOST LEASE.

Plugged through: TBG

District: 02

Signed B. J. Hope  
(TECHNICIAN)