

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-10015-00-00
Spot: NWSEW Sec/Twnshp/Rge: 18-30S-8W
1650 feet from N Section Line, 1650 feet from W Section Line
Lease Name: MESSENGER B Well #: 4-18
County: KINGMAN Total Vertical Depth: 4333 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4332	2505	350 SX
SURF	8.625	408		275 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/28/2015 12:00 AM

Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.

Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER

Witness Type: PARTIAL

Date/Time Plugging Completed: 10/01/2015 4:00 PM

KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

CIBP @ 4228' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2505' PULLED CASING. RAN TUBING INTO 1334', PUMPED 300 LBS OF MUD THEN SPOTTED 35 SX OF CEMENT AND 100 LBS OF HULLS. PULLED TUBING TO 842' SPOTTED 35 SX OF CEMENT. PULLED TUBING TO 431' CIRCUALTED TO SURFACE WITH 180 SX OF CEMENT. CEMENT FELL BACK 90' TOPPED OFF WITH 25 SX OF CEMENT.

KCC WICHITA
NOV 17 2015
RECEIVED

Remarks: CEMENT ALLIED. DENIED TA LOST LEASE.

Plugged through: TBG

District: 02

Signed B. J. Hope

(TECHNICIAN)