

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-10017-00-00
Spot: NWNENE Sec/Twnshp/Rge: 18-30S-8W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: MESSENGER D Well #: 2-18
County: KINGMAN Total Vertical Depth: 4297 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4296	1480	150 SX
SURF	8.625	408		275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2015 12:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 10/07/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP @ 4152' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 1480' PULLED CASING. RAN TUBING INTO 1336', SPOTTED 35 SX OF CEMENT AND 100 LBS OF HULLS. PULLED TUBING TO 870' SPOTTED 35 SX OF CEMENT. PULLED TUBING TO 466' CIRCULATED TO SURFACE WITH 180 SX OF CEMENT. CEMENT FELL BACK 49' TOPPED OFF WITH 20 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
4202	4265		

KCC WICHITA
NOV 17 2015
RECEIVED

Remarks: CEMENT ALLIED. DENIED TA LOST LEASE

Plugged through: TBG

District: 02

Signed B. J. Hope
(TECHNICIAN)

JK