

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20917-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 35-34S-33W
5091 feet from S Section Line, 1027 feet from E Section Line
Lease Name: BOX Well #: 1
County: SEWARD Total Vertical Depth: 6804 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1650		
CIBP		6138		
PROD	4.5	6470	0	WITH 450 SX CMT
SURF	8.625	1601		WITH 600 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/16/2015 10:30 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Revd. from: DALLAS J PRESTON Company: EDISON OPERATING Phone: (620) 886-0612

Proposed Plugging Method: RUN TBG TO 3175' & PUMP 50 SX CMT. CIBP @ 1650'. RUN BOND LOG, IF NO CMT PERFORATE AT 1625'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: PARTIAL
Date/Time Plugging Completed: 10/21/2015 3:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

RUN TBG TO 3175' & PUMP 50 SX CMT. SET CIBP @ 1650'. PERFORATE AT 1625. PUMPED 350 SX CMT. CMT DID NOT CIRCULATE. 10/19/15: TAGGED CMT AT 540'. 10/20/15: PERFORATE AT 510'. PUMPED 150 SX CMT. CMT DID NOT CIRCULATE. 10/21/15: TAGGED TOC @ 200'. RAN TBG TO 180'. CIRCULATED TO SURFACE INSIDE 4 1/2" WITH 20 SX CMT. PUMPED 180 SX CMT DOWN THE ANNULUS & PRESSURED TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
6291	6307		
6010	6024		
5428	5432		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed [Signature]
S/A

RECEIVED
OCT 30 2015
KCC DODGE CITY

(TECHNICIAN)
KCC WICHITA

NOV 12 2015
RECEIVED