

State of Kansas



15-047-00253-0000

FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 22 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Deacon of Forbes Casing Pulling has this date requested permission to plug the following described well:

Mr. Deacon guarantees payment of the plugging fee.

Operator's full Name: Sunray DX

Complete Address: 321 W. Douglas, Wichita, 2 Kansas

Lease Name: Gus Edwards Well No. # 1

Location: C SW SW Sec. 35 Twp. 26 Rge. 19 (E) (W) W

County Edwards Total Depth 5012 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Deacon was instructed to plug the well as follows:

329' of 8 5/8" surface pipe cement circulated. 5004' of
5 1/2" long string cemented with 300 sacks. Plugged back to
4219'. Perforated 4196' to 4202'. Sand to 4180', cement
with 5 sacks. Fill hole to 200', 10' rock bridge, cement
with 20 sacks. Fill hole with mud to 40', 10' rock bridge,
cement to base cellar with 10 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent