

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

RECEIVED STATE CORPORATION COMMISSION

APR 6 1960

CONSERVATION DIVISION Wichita, Kansas

4-6-60

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date March 15, 1960, authorized the following plugging operation:

Operator's Full Name: Moharak Drilling Development

Complete Address: Box 624 Hutchinson Kansas

Lease Name: Wedelin Well No. 1

Location: NE. NW. SW. Sec. 25 Twp. 24 Rge. 8 (E) (W) X

County: Reno Total Depth: 3887'

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

T.D. 3887' - S.P. 8 5/8" - 219' C.W.C. 150#

Heavy mud to 210 set plug use 1/4" shells

15# cement through drill pipe, mud to

40' set plug use 1/4" shells 10# cement

to base of cellar.

Bridge rat hole, use shells & 2# cement

Very truly yours,

Signed: Fred W Hampel
Conservation Division Agent