

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

August 26, 1973

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1973
CONSERVATION DIVISION
Wichita, Kansas
8-28-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Cameron of H-30 Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: Hershberger Enterprises, Inc.

Complete Address: Suite 230 - 200 W. Douglas, Wichita, Kansas 67202

Lease Name: O'Hara Well No. 1

Location: SE SE SW Sec. 30 Twp. 24 Rge. 7 (E)(W) X

County: Ellsworth Total Depth 2078' Oil Well

Gas Well Input Well EWD Well D & A X Lost Hole

Mr. Cameron was instructed to plug the well as follows:

Fill hole with mud. Push plug to 400' and pump 40
sacks cement through drill pipe at 400'. Pump 25 sacks
cement through drill pipe at 200'. Push plug and
1/4 sack balls to 40' and cap hole with 10 sacks cement.
Bridge rat hole and cement with 2 sacks cement.

Very truly yours,

Walter J. Torrey
Conservation Division Agent