

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

May 26, 1965

RECEIVED
 STATE CORPORATION COMMISSION

JUN 1 1965

6-1-65

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Ed. Weiler of Shields Drlg. Co., Inc. has this
 date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: T. O. Gaskill

Complete Address: 633 Beacon Bldg., Tulsa, Oklahoma

Lease Name: Deck Well No. 1

Location: NE SW NW Sec. 9 Twp. 24 Rge. 8 (E) (W) X

County Reno Total Depth 3766' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weiler was instructed to plug the well as follows:

Fill hole with mud to 250'. Push plug and $\frac{1}{4}$ sack hulls to
250' and cement hole with 25 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and $\frac{1}{2}$ sack hulls to
40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent