

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

July 27, 1973

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 3 1973 8-3-73

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Cameron of H-30 Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: Hershberger Enterprises, Inc.

Complete Address: 200 W. Douglas, Wichita, Kansas 67202

Lease Name: Dykes Well No. 1

Location: SW SW SW Sec. 20 Twp. 24 Rge. 7 (E) (W) X

County: Reno Total Depth 2110' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cameron was instructed to plug the well as follows:

Fill hole with mud. Push Plug + 1/2 sack bulls to 400' and pump 35 sacks cement through drill pipe at 400'. Pump 25 sacks cement through drill pipe at 200'. Push plug and 1/2 sack bulls to 40' and cap hole with 10 sacks cement. Bridge rat hole and cement with 2 sacks cement

Very truly yours,

Arthur J. Loman
Conservation Division Agent