

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-21047-00-02
Spot: NENW Sec/Twnshp/Rge: 34-29S-34W
4304 feet from S Section Line, 3316 feet from E Section Line
Lease Name: MURPHY D Well #: 2
County: HASKELL Total Vertical Depth: 5600 feet

Operator License No.: 34545
Op Name: ELM III OPERATING COMPANY LLC
Address: 1249 E. 33RD
EDMOND, OK 73013

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4500		
CIBP		5419		
PROD	5.5	5476	1868	WITH 200 SX CMT
SURF	8.625	1818		WITH 450 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/29/2015 1:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP BOTTOM WITH 25 SX CMT & HULLS. PLUG AT 1850' WITH 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: PARTIAL
Date/Time Plugging Completed: 10/29/2015 4:20 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

PUMPED BOTTOM WITH 25 SX CMT & 150# HULLS. PRESSURED TO 500 PSI. 1ST PLUG AT 1860' WITH 50 SX CMT. 2ND PLUG AT 726' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4706	5350		
4334	4338		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed [Signature]

SA

(TECHNICIAN)
KCC WICHITA

NOV 12 2015

RECEIVED

RECEIVED
OCT 30 2015
KCC DODGE CITY [Signature]