

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-20955-00-00
Spot: NESW Sec/Twnshp/Rge: 29-24S-18W
1980 feet from S Section Line, 3300 feet from E Section Line
Lease Name: DERLEY Well #: 1-29
County: EDWARDS Total Vertical Depth: 4700 feet

Operator License No.: 34402
Op Name: GARAL, DONNA AND VINCENT INNON
Address: 30-38 48 ST
ASTORIA, NY 11103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4655	1800	WITH 200 SX CMT
SURF	8.625	332		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/03/2015 10:15 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 4300' WITH 4 SX CMT. PLUG AT 1320' WITH 12 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/03/2015 11:30 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

SAND BACK TO 4280' & PUT 4 SX CMT ON TOP WITH BAILER. 1ST PLUG AT 1320' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4353	4358		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
NOV - 6 2015
KCC DODGE CITY

KCC WICHITA
NOV 12 2015
RECEIVED