

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23740-00-00
Spot: SEWNESW Sec/Twnshp/Rge: 33-32S-13W
1990 feet from S Section Line, 1852 feet from W Section Line
Lease Name: RUCKER Well #: 1
County: BARBER Total Vertical Depth: 5096 feet

Operator License No.: 34449
Op Name: HALLELUJAH-EL SHADDAI OIL, LLC
Address: 103 S. NINNESCAH
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4450		WITH 2 SX CMT
PROD	5.5	4735	1707	WITH 100 SX CMT
SURF	10.75	254		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2015 9:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: ROBIN BROWN Company: HURRICANE SERVICES Phone: (316) 262-1077

Proposed Plugging Method: SET CIBP @ 4425' WITH 2 SX CMT. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 290' WITH 75 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2015 10:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4450' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 613' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 273' WITH 75 SX CMT. 3RD PLUG AT 60' WITH 80 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4473	4490		

Remarks: USED 60/40 POZMIX 4% GEL BY HURRUCANE SERVICES.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
NOV - 4 2015
KCC DODGE CITY

KCC WICHITA
NOV 12 2015
RECEIVED

Form CP-2/3